

## Questions & Responses

**PROFESSIONAL SERVICE PROVIDER**  
**Request for Qualifications Number 2019-040**  
**PROFESSIONAL ENGINEERING/PROJECT MANAGEMENT SERVICES FOR**  
**KILLEEN TEMPLE METROPOLITAN PLANNING ORGANIZATION**  
**PROGRAM CATEGORY 7; Project Description:**  
**Nolanville Park Connectivity**

**City Response is in RED**

1. The Project Scope indicates “stabilizing and widening the edges of Avenue H (from 10<sup>th</sup> Street to Jackrabbit Road) extending throughout the length of Mesquite Street”. We are not clear if this means that Avenue H will get widened all the way from 10<sup>th</sup> to Jackrabbit Road or from 10<sup>th</sup> to Mesquite and then all of Mesquite, or both. Please clarify.

Preliminary Engineering will include stabilizing and widening the whole length of Avenue H from 10<sup>th</sup> Street to Jackrabbit and then the whole length of Mesquite.

TxDOT portion only includes 10<sup>th</sup> Street to Mesquite and then all of Mesquite. (The City may be interested in completed the remainder of Avenue H at the time of the project construction or a future date.)

2. Is it anticipated that additional right-of-way, easements, or temporary construction easements will need to be acquired for this work?

It is not anticipated, a survey of Avenue H was completed by ACS showing that there is enough ROW to complete the project.

3. Will 10-foot wide sidewalk be constructed on one or both sides of Avenue H? If only one side, which side?

The 10ft path is anticipated to work best on the North Side (Westbound lane).

4. There are significant drainage swales on both sides of Avenue H. Is the intent to maintain this drainage as open channel or install storm sewer? Available ROW may limit the ability to maintain surface drainage and have a 10-foot sidewalk.

It is expected that the drainage will remain open. The City would like to consider improvement especially where Mesquite and Avenue H connect.

5. Will all of the limits of Avenue H get an asphalt overlay on the entire road (similar to the Old Nolanville Rd Project)?

Yes

6. Are there any pavement improvements (curb, overlay, widening, etc.) planned for Mesquite, or does it only consist of striping the shared use path?

Ideally, ribbon curbing would be added to Mesquite. There is an overlay from Paveway Systems that we would like to consider to mark the shared use path. Additional pavement overlay is not anticipated.

7. Project schedule indicates letting the project in FY 21 and constructing in FY 22. Does that mean that the project needs to advertise by August 2021?

Yes, advertise in August 2021 and construct January 2022. However, Advanced Funding Agreement is still pending from TxDOT.

8. The number for the bid shows as 2019-040 in public notices, but on the NOI document is listed as 2019-010. Which number is correct?

2019-040 is the number that will be used for this NOI. Proposals with 2019-010 will still be accepted. This will ensure future public information requests are referencing the number used to advertise the NOI.