

Bid Form
Ave H Channel Improvements
Phase One
City of Nolanville, Texas

April 21, 2026

Item	Description	Unit	Quantity	Unit Price Numerals	Total
1	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Bonds and Mobilization</u> and in place <div style="text-align: right;"> _____ Dollars _____ Cents </div> Per Lump Sum	L.S.	1.00		
2	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Stormwater Pollution Prevention Plan Including Record Keeping</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents </div> Per Lump Sum	L.S.	1.00		
3	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Stabilized Construction Entrance</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents </div> Per Lump Sum	L.S.	1.00		
4	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Silt Fence</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents </div> Per Linear Foot	L.F.	750.00		
5	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Channel Excavation</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents </div> Per Bank Cubic Yard	B.C.Y.	930.00		
6	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Channel Slope Fill</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents </div> Per Bank Cubic Yard	B.C.Y.	100.00		
7	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Northridge Pond Excavation including Rain Garden Excavation and Incidental Fills</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents </div> Per Bank Cubic Yard	B.C.Y.	425.00		

Bid Form
Ave H Channel Improvements
Phase One
City of Nolanville, Texas

April 21, 2026

Item	Description	Unit	Quantity	Unit Price Numerals	Total
8	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Northridge Pond Outlet Structure (Poured in Place Concrete)</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents Per Cubic Yard </div>	C.Y.	22.80		
9	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Maccaferri Reno Mattresses</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents Per Cubic Yard </div>	C.Y.	142.00		
10	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Rain Garden Drainage Pipe System (Including Rock Matrix and Filter Fabric)</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents Per Lump Sum </div>	L.S.	1.00		
11	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Rain Garden Scupper</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents Per Square Foot </div>	S.F.	485.00		
12	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Rain Garden Arcosa Fine Lightweight Aggregate</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents Per Each </div>	B.C.Y.	75.00		
13	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Rain Garden Blended Planting Soil</u> complete and in place <div style="text-align: right;"> _____ Dollars _____ Cents Per Each </div>	B.C.Y.	175.00		

Bid Form
Ave H Channel Improvements
Phase One
City of Nolanville, Texas

March 1, 2026

Item	Description	Unit	Quantity	Unit Price Numerals	Total
14	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Rain Garden Plantings From Plant List and Two Crepe Myrtles</u> complete and in place _____ Dollars _____ Cents Per Square Foot	S.F.	1.00		
15	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Vetiver Erosion Control Plantings</u> complete and in place _____ Dollars _____ Cents Per Square Foot	S.F.	800.00		
16	Furnish and install all material, machinery, labor, overhead, and profit to provide <u>Demobilization and Final Cleanup</u> complete and in place _____ Dollars _____ Cents Per Lump Sum	L.S.	1.00		
	Ave. H Channel Improvements Phase One Total Bid				

Bid Form
Ave. H Channel Improvements
Phase One

April 21, 2026

City of Nolanville, Texas

Total Amount of Bid (In Words)

Total Amount of Bid (In Figures)

--

Receipt is hereby acknowledged of the following addenda to the contract documents.	
Addendum #1 Dated _____	Received _____
Addendum #2 Dated _____	Received _____
Addendum #3 Dated _____	Received _____

Date: _____	_____
-------------	-------

	Contractor
--	------------

Seal and Authorization (If a Corporation)	By
--	----

	Title
--	-------

Attest:	Address
---------	---------

Secretary	City & State
-----------	--------------

	Telephone
--	-----------